



SCOPE CONFIRMATION · PREPARED FOR QUOTATION

Mitchell Residence

Stirling, SA 5152

PREPARED FOR
Sarah & Tom Mitchell

INSPECTED
8 October 2026

PREPARED BY
Alex Morgan

ISSUED
10 October 2026

This scope records the proposed work to be priced. It is not a quotation, contract or final construction specification.

Renovate the existing kitchen, main bathroom and living room. Retain the existing exterior. Confirm all measurements and selections before quotation.

AREA 01 · PROPOSED WORKS

Kitchen

DIMENSIONS

Length 4.2 m · Width 3.8 m · Ceiling height 2.7 m

REFERENCE PHOTOS



Fig 1.1 – Existing U-shaped kitchen with cream laminate cupboards, wall oven, electric cooktop, tiled splashback and stainless double sink.



Fig 1.2 – The same kitchen, closer to the sink and aluminium window; laminate bench and original tiled splashback.



Fig 1.3 – Close-up of worn brass-look kitchen cupboard handles and cream laminate cabinet edges.

- Remove the cream laminate cupboards, benchtop, sink and tiled splashback.
- Supply replacement joinery, stone benchtops and tiled splashback.
- Make required plumbing and electrical alterations.

BY OWNER

- Oven, cooktop and dishwasher.

TO CONFIRM

- Appliance models, service locations and cabinetry selections.

SELECTIONS & SCOPE DETAILS

- kitchen layout: Change within this room
- What cabinetry work is: Replace all cabinetry
- Cabinet door style: Shaker
- Benchtop work: Replace
- Splashback material: Tiles
- Sink: Stainless steel
- Tapware: Mixer
- Appliances: Oven, Induction cooktop, Dishwasher
- Floor finish: Tiles
- Island bench: Included

Kitchen – continued

- Lighting: Downlights, Pendants

AREA 02 · PROPOSED WORKS

Main Bathroom

DIMENSIONS

Length 3.1 m · Width 2.4 m · Ceiling height 2.7 m

REFERENCE PHOTOS



Fig 2.1 – Clean original bathroom with shower over the bath, cream tiles, timber-look vanity and terracotta floor.



Fig 2.2 – Closer view of the same shower-over-bath, chrome shower head, curtain and window.



Fig 2.3 – Close view of the same timber-look vanity, cream basin, chrome fittings and mirror cabinet.

- Remove existing shower-over-bath fittings, vanity and tiled finishes.
- Install new waterproofing, shower, vanity and tiles.

Main Bathroom – continued

TO CONFIRM

- Shower screen dimensions, fixtures and any substrate repairs.

SELECTIONS & SCOPE DETAILS

- Bath: No bath
- Shower screen: Semi-frameless
- Shower niche: Included
- Vanity: Wall-hung
- Vanity top: Stone
- Shower head: Wall-mounted

AREA 03 · PROPOSED WORKS

Living Room

DIMENSIONS

Length 5.0 m · Width 4.2 m · Ceiling height 2.7 m

REFERENCE PHOTOS



Fig 3.1 – Living room overview with beige carpet, cream walls and sliding door to the covered patio.



Fig 3.2 – Second angle across the same room, with modern furniture and existing older finishes.



Fig 3.3 – Reverse view from the patio side toward the hallway, room entrance and retained wall finishes.

- Prepare and repaint walls and ceiling.
- Replace selected floor finishes.

Living Room – continued

- Protect the existing sliding door and windows.

Exterior and access

- Retain brickwork, roof, garden and rear pergola.
- Protect driveway and side access during construction.

CLIENT REVIEW · BEFORE QUOTATION

Is this what you want priced?

Please check that the areas and work described in this document match what you want included in the quotation. Advise the builder of any additions, removals or corrections before pricing begins.