



RENOVATIONS & EXTENSIONS

SCOPE CONFIRMATION · PREPARED FOR QUOTATION

Hills renovation

24 Sample Lane, Adelaide Hills SA

PREPARED FOR
Alex Bennett

PREPARED BY
Jordan Lee

SITE VISIT
7 October 2026

ISSUED
7 October 2026

This scope records the proposed work to be priced. It is not a quotation, contract or final construction specification.

AREA 01 · PROPOSED WORKS

Kitchen

DIMENSIONS

Length 4.2 m

Width 3.6 m

Ceiling height 2.7 m

Floor area: 15.12 m² (length × width)

Proposed works

- Keep the current kitchen layout and replace all cabinetry, including the island.
- Install shaker doors in laminate finish, stone benchtops and a tiled splashback.
- Fit a stainless steel sink and mixer; reconnect plumbing at existing locations.
- Lay new floor tiles and reconnect the existing appliances.
- Provide downlights and pendants above the island.

To confirm

- Final cabinet colour, stone colour and tile selection.

SELECTIONS & SCOPE DETAILS

- Is the kitchen layout changing: Keep current layout
- Appliances: Keep existing
- Island bench: Included
- Electrical work required: Included
- Lighting: Downlights, Pendants

Kitchen – continued

REFERENCE PHOTOS



Fig 1.1 – Kitchen – existing room



Fig 1.2 – Oven and cooktop



Fig 1.3 – Sink and benchtop

AREA 02 · PROPOSED WORKS

Ensuite

DIMENSIONS

Length 3.0 m

Width 2.2 m

Ceiling height 2.7 m

Floor area: 6.60 m² (length × width)

Proposed works

- Strip out the existing ensuite and prepare for new waterproofing and tiling.
- Install a wall-hung vanity with stone top, mirror cabinet and back-to-wall toilet.
- Install a single-panel shower screen, niche and rail shower.
- Tile the floor and walls to full height. Replace tapware and exhaust fan.

To confirm

- Vanity width, shower screen dimensions and tapware finish.

SELECTIONS & SCOPE DETAILS

- Bath: No bath
- Floor finish: Tiles
- Underfloor heating: Not included
- Heated towel rail: Not included

REFERENCE PHOTO



Fig 2.1 – Ensuite – existing room

AREA 03 · PROPOSED WORKS

Living room

DIMENSIONS

Length 5.6 m

Width 4.4 m

Ceiling height 2.7 m

Floor area: 24.64 m² (length × width)

Proposed works

- Install hybrid flooring and paint the walls and ceiling.
- Replace the downlights and retain the existing fireplace.

To confirm

- Flooring colour, paint colours and downlight positions.

SELECTIONS & SCOPE DETAILS

- Feature wall: None
- Fireplace: Keep existing

AREA 04 · PROPOSED WORKS

Laundry

DIMENSIONS

Length 2.8 m

Width 1.9 m

Ceiling height 2.7 m

Floor area: 5.32 m² (length × width)

Proposed works

- Replace cabinetry with flat laminate doors and a laminate benchtop.
- Install a stainless steel trough and mixer; reconnect plumbing.
- Provide side-by-side washer and dryer spaces and new floor tiles.

To confirm

- Appliance dimensions, joinery colour and tile selection.

SELECTIONS & SCOPE DETAILS

- What cabinetry work is required: Replace all cabinetry

PROJECT-WIDE MATTERS

Project overview

Renovate the kitchen, ensuite, living room and laundry. Retain the existing room layouts. Protect retained finishes during the works.

CLIENT REVIEW · BEFORE QUOTATION

Is this what you want priced?

Please check that the areas and work described in this document match what you want included in the quotation. Advise the builder of any additions, removals or corrections before pricing begins.